

		Kennedy Industries 4925 Holtz Dr. Wixom, MI 48393		KSB Dubric 3737 Laramie Dr. NE Comstock Park, MIO 49321		Detroit Pump 23751 Amber Ave. Warren, MI 48089		JETT Pump & Valve LLC 4770 Pontiac Lake Rd. Waterford, MI 48328										
Quantity	Description	Unit Price	Total Price	Unit Price	Total Price	Unit Price	Total Price	Unit Price	Total Price									
3	Submersible dry pit Sewage pumps with 8"Discharge and 12"suction 60hp,3phase,460volts	\$ 63,433.33	\$ 190,299.99	\$ 38,923.00	\$ 116,769.00	\$ 37,221.00	\$ 111,663.00	\$ 40,500.71	\$ 121,502.13									
3	Submersible dry pit stands with 12" inlet elbow	\$ 4,550.00	\$ 13,650.00	Included in pump price		\$ 10,462.00	\$ 31,386.00	\$ 2,236.19	\$ 6,708.57									
3	Mini-Cas Seal Fail, high Temp Monitoring Relay	\$ 600.00	\$ 1,800.00	included in pump price		\$ 295.00	\$ 885.00	\$ 974.78	\$ 2,924.34									
3	18" Dezurik Knife Gate Valve, flanged end connection, 316ss Cast body, Ptfе packing, 316ss gate, with hand wheel operator.	\$ 5,683.33	\$ 17,049.99	\$ 7,567.00	\$ 22,701.00	\$ 7,983.00	\$ 23,949.00	\$ 11,260.61	\$ 33,781.83									
3	8" apco Swing Check valve, Flanged end to connection with lever weight.	\$ 1,233.33	\$ 3,699.99	\$ 2,334.00	\$ 7,002.00	\$ 2,289.00	\$ 6,867.00	\$ 2,649.65	\$ 7,948.95									
3	8" Dezurik plug valve, flanged end connection, cast iron body and G-series gear with hand wheel operator.	\$ 1,666.67	\$ 5,000.01	\$ 2,688.00	\$ 8,064.00	\$ 1,595.00	\$ 4,785.00	\$ 1,653.71	\$ 4,961.13									
Additional Fees					\$ 10,921.00													
TOTAL BID			\$ 231,499.98		\$ 165,457.00		\$ 179,535.00		\$ 177,826.95									
We propose to deliver the (Brand & Model)		See below		KSB KRT D 200-400/456XFG-D		ABS/Sulzer XFP 200J-CH2 PE 350/6		WILO EMU FA/KENNEDY/SUREFLOW										
No later than (Delivery Date)		See below		30-32 weeks after approved submittals		24 weeks from date of full release		22-26 WEEKS ARO										
Flygt 3202-16 Week Lead Time After Approval				KSB DUBRIC IS TAKING EXCEPTION TO SPEC.				JETT PUMP IS TAKING EXCEPTION TO SPEC.										
18" Dezurik Knife Gate Valves-16 Weeks After Approval				Page S 1 of 7, Testing, C. NOT STANDARD FOR DRY PIT DESIGN				<table border="1"> <thead> <tr> <th>Num</th> <th>Reference</th> <th>Clarification/Exception</th> </tr> </thead> <tbody> <tr> <td>1</td> <td>Pump Construction</td> <td>Wilо exterior paint will be epoxy. Wilо standard motor design with cast iron cooling jacket.</td> </tr> <tr> <td>2</td> <td>Cable Entry</td> <td>Wilо cable entry will be epoxy-potted and approved for the explosion-proof rating.</td> </tr> </tbody> </table>		Num	Reference	Clarification/Exception	1	Pump Construction	Wilо exterior paint will be epoxy. Wilо standard motor design with cast iron cooling jacket.	2	Cable Entry	Wilо cable entry will be epoxy-potted and approved for the explosion-proof rating.
Num	Reference	Clarification/Exception																
1	Pump Construction	Wilо exterior paint will be epoxy. Wilо standard motor design with cast iron cooling jacket.																
2	Cable Entry	Wilо cable entry will be epoxy-potted and approved for the explosion-proof rating.																
8" Dezurik Plug Valves-2 Weeks After Approval				Page S 4 of 7, Mechanical Seals, UPGRADE TO SEAL FACES OF SILICON CARBIDE														
8" Apco Swing Check Valves-21 Weeks After Approval				Page S 5 of 7, Pump Shaft, STANDARD CAST ASTM 45 CAST IRON														
				Page S 5 of 7, Volute/Suction Cover, "the volate shall..." NOT INCLUDED														

Kennedy Industries 4925 Holtz Dr. Wixom, MI 48393	KSB Dubric 3737 Laramie Dr. NE Comstock Park, MIO 49321	Detroit Pump 23751 Amber Ave. Warren, MI 48089	JETT Pump & Valve LLC 4770 Pontiac Lake Rd. Waterford, MI 48328		
ALTERNATE: 8" AVK Swing Check Valves-3 Weeks After Approval. \$12,900.00 total for (3) valves.	Page S 5 of 7, Protection, second paragraph, "Mini CAS" replace with KSB PUMP SAFE MODULE Page S 5 of 7, Dry Pit Vertical Base, THE FOUNDATION RAIL SET WILL REQUIRE CONTRADCTOR TO POUR THE CONCRETE FOUNDATION. Page S 6 of 7, Start-Up Service, i, NOT INCLUDED Page S 6 of 7, Warranty, DELETE "In the event that the repair..." Page S 7 of 7, Submittal, O&M and Start Up Data, "on an FTP Site..." replaced with WILL BE ON DROP BOX FOR ACCESS 24/7.		3	Explosion Proof	Wilo standard motor design is approved for the explosion-proof rating. Starts per hour 15 maximum. Service factor 1.10.
			4	Cooling System	Wilo standard motor design with cast iron cooling jacket.
			5	Power/Sensor Cable	Determination of cable compliance with VFDs and correcting interference via electrical conduits as required shall be by electrical contractor or similar. Wilo electrical cables cannot be changed in order to maintain the FM explosion-proof rating.
			6	Mechanical Seals	Wilo will provide standard double mechanical seals in a single housing with silicon-carbide faces. Silicon-carbide is harder than tungsten-carbide. Wilo will provide our standard motor design, competitor designs are not available.
			7	Pump Shaft	Shaft will be AISI 420SS.
			8	Impeller	Impeller will be Wilo standard design constructed of ductile iron and protected by a ceramic coating for corrosion and abrasion resistance.
			9	Volute	Volute will be Wilo standard design constructed of cast iron and protected by a ceramic coating for corrosion and abrasion resistance. Wilo standard design wear rings.

Kennedy Industries 4925 Holtz Dr. Wixom, MI 48393	KSB Dubric 3737 Laramie Dr. NE Comstock Park, MIO 49321	Detroit Pump 23751 Amber Ave. Warren, MI 48089	JETT Pump & Valve LLC 4770 Pontiac Lake Rd. Waterford, MI 48328		
			10	Protection	Wilo recommends monitoring of the external moisture probe/electrode for an earlier detection of moisture intrusion. Wilo-compatible relays are required, MiniCAS is not compatible.
			11	Clog-free	
			12	Start-up Service	
			13	Warranty	Loaner pump not by Wilo. Nameplate will be Wilo standard.
			14	Submittal, O&M	